



STANDARD STORM WATER POLLUTION CONTROL NOTES

Concrete Washout

- Contractor shall establish and use an adequately sized concrete washout area to contain washout wastes on site. It is illegal to wash concrete, slurry, mortar, stucco, plaster and the like into the stormwater conveyance system or any receiving water. Contractor shall post a sign designating the washout location.

Construction Site Access

- A stabilized construction site access shall be provided for vehicles egress and ingress to prevent tracking dirt off site. This shall include using material such as gravel and/or corrugated steel panels/plates.

Construction Vehicles

- A specific area away from gutters and stormdrain shall be designated for construction vehicles parking, vehicle refueling, and routine equipment maintenance. All major repairs shall be made off-site.

Erosion Control

- Erosion control must be provided for all erosive surfaces. Sloped surfaces especially shall be protected against erosion by installing erosion resistant surfaces such as erosion control mats, adequate ground cover vegetation, and bonded fiber matrix.
- No excavation and grading activities are allowed during wet weather.
- Diversion dikes shall be constructed to channel runoff around the construction site. Contractor shall protect channels against erosion using permanent and temporary erosion control measures.
- Remove existing vegetation only when absolutely necessary. Large projects shall be conducted in phases to avoid unnecessary removal of the natural ground cover. Do not remove trees or shrubs unnecessarily; they help decrease erosion.
- Temporary vegetation must be planted on slopes or where construction is not immediately planned for erosion control purposes. Erosion shall be prevented by planting fast-growing annual and perennial grasses to shield and bind the soil.
- Plant permanent vegetation as soon as possible, once excavation and grading activities are complete.
- Water usage for dust control shall be minimized.

On-site Construction Material Storage

- Stored materials shall be contained in a secure place to prevent seepage and spillage. Contractor shall store these products where they will stay dry out of the rain. Contractor shall provide secondary containment for all fuel stored on-site.
- Eliminate or reduce pollution of stormwater from stockpiles kept on-site. Stockpiles may include soil, paving materials, asphalt concrete, aggregate base, etc. Stockpiles shall be located away from concentrated stormwater flows and stormdrain inlets. Stockpiles shall be covered or protected with soil stabilization measures and provided with a temporary sediment barrier around the perimeter at all times.

Training

- Contractors' employees who perform construction in the City of Encinitas shall be trained to be familiar with the City of Encinitas stormwater pollution control requirements. These BMP notes shall be available to everyone working on site. The property owner(s) and the prime contractor must inform subcontractors about stormwater requirements and their own responsibilities.

Waste Management

- Contractor shall be responsible for properly disposing of all waste and unused construction materials. Dumping of unused or waste products on the ground, where water can carry them into the conveyance system is strictly prohibited.
- No seepage from dumpsters shall be discharged into stormwater. Berms/dikes shall be placed around dumpsters to divert the natural storm runoff. Dumpsters shall be checked frequently for leaks. Dumpster lids shall remain closed at all times. Dumpsters without lids shall be placed within structures with impervious roofing or covered with tarps in order to avoid rain contact with any trash material.
- Many construction materials, including solvents, water-based paints, vehicle fluids, broken asphalt and concrete, wood, and cleared vegetation can be recycled. Non-recyclable materials must be taken to an appropriate landfill or disposed of as hazardous waste. For information on disposal of hazardous material, call the **Hazardous Waste Hotline** toll free at (800) 714-1195. For information on landfills and to order dumpsters call **EDCO** at (760) 436-4151.
- Pollutants shall be kept off exposed surfaces. Place trash cans and recycling receptacles around the site.
- Portable toilets must be in good working order and checked frequently for leaks. Contractor shall provide secondary containment and locate portable toilets away from stormdrain inlets on pervious surfaces.